



Value Engineering Study on Canal Rehabilitation Work Using Cultures in Samarinda Ulu District

Ibnu Khaldun¹, Wateno Oetomo², Risma Marleno³

^{1,2,3}Fakultas Teknik Universitas 17 Agustus 1945 Surabaya Correspondent author: <u>s2zay@gmail.com</u>

Abstract: This research was conducted with the aim of analyzing the Engineering Value of Drainage and Culvert Rehabilitation Work in Samarinda Ulu District. The settlement method for this calculation uses Value Engineering Analysis. Value Engineering Analysis is carried out when the Budget Plan (RAB) is still being planned to get maximum results. This research method was carried out in five stages of Value Engineering, namely the information stage, function analysis stage, creative stage, evaluation stage and presentation stage. Weight of each criterion using the Zero-One Method. Zero-One Analysis Matrix Method The zero-one method is used for weighting and assigning scores to criteria. From the results of the analysis, it was found that the best alternative that can replace the initial implementation method for selected work items in concrete work is Precast Reinforced Concrete Partially Cast Ready Mix Reinforced Concrete. The cost of concrete work, namely at the beginning or according to plan, is Rp. 623,679,984.00 Costs for concrete work after VE, namely Rp. 271,933,824.09 With costs saved amounting to Rp. 352,393,548.00 or 18.3%. The overall project cost for the initial plan is Rp. 2,099,885,844 while the overall cost of the project after VE is IDR 1,748,139,684. With the cost savings of Rp. Rp. 352,393,548.00 or 16.78% of the total project.

Key word: Value Engineering, Zero-One Methode, concrete work, Matrix Method

INTRODUCTION

The main problem with urban drainage is flooding, which is a very common issue in big cities, especially during the rainy season. Almost all cities in Indonesia experience flooding every year, and this problem has not been resolved and tends to worsen in terms of frequency, depth and duration. To overcome this problem, management is needed which includes planning a good drainage system, making detailed plans, restructuring institutions and related regulations, as well as community participation in overcoming drainage problems. Cities are places for many activities, so to ensure the health and comfort of residents, adequate sanitation is needed, such as drainage. Drainage helps drain pools of rainwater to prevent flooding and reduce health impacts and disruption of community activities (Halim, 2011). Drainage is a facility created to reduce excess surface water from rain, seepage, or excessive irrigation. With increasing population and infrastructure development, the need for drainage also increases (Suripin, 2004). The city of Samarinda faces the problem of waterlogging when it rains in several areas due to damaged drainage channels, such as in Samarinda Ulu. This damage causes water flow not to flow smoothly and accumulation of sediment at the bottom of the channel. Wesli (2008) stated that high intensity rainfall causes excess water which results in puddles, which if not immediately resolved, will disrupt community activities.

The Samarinda regional government is carrying out a vital drainage project and requires a large budget, so planning the work from start to finish must use value engineering methods to evaluate the cost performance of the project. This research aims to analyze Value Engineering in drainage channel rehabilitation work in Samarinda Ulu District.

Projects are temporary activities that last for a certain period of time with specific resource allocation to achieve certain goals (Rifai & Soekiman, 2014). Construction projects include all activities related to development, such as buildings, civil infrastructure (roads, water structures, docks), and installations. Value Engineering is a multidisciplinary, systematic and structured decision-making process. This involves analyzing functions to achieve the best value for a project by defining the functions required to achieve the desired value at optimal cost, consistent with the required quality and performance (Berawi, 2013). Drainage, from the word 'to drain' which means to drain or drain water, refers to a system that handles excess water, both above and below the ground surface. Urban drainage is a system within a city area that functions to control or reduce excess surface water in residential areas from local rain, so that it does not disturb the community and is beneficial for human life. Generally, urban areas have a distance between buildings of no more than 200 meters and a population of more than 2000 people (Angelakis et al., 2017).

METHODOLOGY

In this research study, the Samarinda Ulu District drainage channel rehabilitation work project will be discussed. The research carried out is quantitative descriptive research, namely research that describes the subject or object being studied using the results of data analysis in the form of numbers, where each stage is the part that determines how to proceed to the next stage. Research begins with an assessment of the problem then refers to a literature review. Based on the literature review, research data was collected consisting of primary data and secondary data. The data is then analyzed using the value engineering method and following several stages until the evaluation and conclusion drawing stage (figure 1).




Figure 1. Research Flow Chart

RESULTS AND DISCUSSION

In this research, the application of value engineering to projects uses an analysis stage called Value Engineering. These stages include the information stage, creative stage, analysis stage, development stage and reporting stage. Data processing in the application of value engineering follows several steps:

- a. Information Stage: Gathering information relating to all aspects of the project.
- b. Creative/Speculation Stage: Looking for alternative jobs that have a large cost/worth value.
- c. Analysis Stage: Filter the advantages and disadvantages of alternatives/creatives. These advantages and disadvantages are analyzed by establishing several assessment criteria.
- d. Development Stage: Developing alternatives that have been selected based on an analysis of advantages and disadvantages.
- e. Reporting/Recommendation Stage: Make a report regarding the activities and results that have been carried out in the value engineering process.
- f. All the stages above will be explained in detail as follows. Information Stage

The project examined in this research is the Drainage Channel Rehabilitation Work project, Samarinda Ulu District. The data collected is in the form of primary data and secondary data. In accordance with the request from the project owner, the RAB value submitted by the contractor was requested to be reanalyzed. At this stage, the work items that have the highest cost down to the lowest cost will be explained.

Function Analysis

No.	Component	Verb	Noun	B/S	Туре	Cost (Rp)	Worth (Rp)	Information
1	Concrete	Channeling	Burden	В	Р	-	-	VE
2	Ironing	Withhold	Burden	В	Р	-	-	-
3	Formwork	Withhold	Concrete	S	S	-	-	-
	AMOUNT					-	-	-

Table 1: Identification of Job Functions

The function analysis as table 1 only explains the work items that will be carried out by VE analysis and definitions of the function of measurable verbs and nouns. The value of the benefits (worth) cannot yet be shown at the cost, because it is done at the creative stage (table 2).

Speculation Stage (Creativity)

Table 2. Calculation of Percentage of Work Items

NO.	JOB DESCRIPTION	TOTAL PRICE (Rp)	PERCENT (%)
A	Preparatory work	101.254.900	4,34
В	Earthworks	272.912.010	11,71
С	Concrete Work	1.452.366.184	62,31
D	Piling Work	67.192.500	2,88

E Iron And Aluminum Works 206.160.250 8,84
--

Here are some alternatives used in VE for concrete work (table 3):

- 1. Initial Design (Precast Reinforced Concrete)
- 2. Partially Precast Reinforced Concrete (Precast)
- 3. Ready mix cast reinforced concrete

Tabel 3.	Value	Engineering	items	alternative
Tuber 0.	value	Linginiconing	nonio	anomativo

Alternative	Job description	Total Price (Rp)	Difference (Rp)	Comparison (%)
	Initial Design (Precast Reinforced Concrete)	623.679.984		
1	Partially Precast Reinforced Concrete	467.106.327	156.573.657	2,98
2	Ready mix cast reinforced concrete	271.286.436	352.393.548	1,77

The largest value was obtained, the percentage difference was 2.98% in alternative 2 in Partially Precast Reinforced Concrete. From the initial information data, the design is intended for K-300 quality concrete specifications. The 2nd largest comparison was obtained in Ready mix Cast Reinforced Concrete with a comparison value of 1.77%.

Analysis

This stage aims to evaluate whether alternative construction replacement ideas have potential advantages and disadvantages through value engineering. The analysis stage aims to select the best design alternative among various ideas or other design ideas as a proposal in the recommendation stage. As a continuation of the creative stage, this stage focuses on analyzing previously generated ideas or ideas.

The assessment in the analysis stage is carried out as objectively as possible. In this research, the analysis was carried out using the Profit and Loss Analysis method. The alternatives obtained from the creative stage are recorded along with their advantages and disadvantages, then given a weighted value (rating). The selection criteria are determined through discussions with the project party, in this case carried out by the Site Engineering Manager. The assessment of each alternative is also carried out by the Site Engineering Manager (table 4).

The following are details of the steps in the analysis stage:

- a) Alternative Identification: Collecting all alternatives generated from the creative stage.
- b) Advantages and Losses Assessment: Each alternative is evaluated to identify potential advantages and disadvantages.
- c) Giving Weighted Value (Rating): Each gain and loss is given a weight or value based on its importance.
- d) Discussion with Project Parties: Assessment criteria and value weights are discussed and agreed with the Site Engineering Manager.
- e) Selection of the Best Alternative: Based on the weight of the values given, the alternative with the highest value is selected as the recommended recommendation.

f) By going through this stage, it is hoped that design alternatives can be selected that provide the best value for the project, taking into account all relevant aspects.

1 Initial Design (Precast Reinforced Concrete) Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process 2 Partially Precast Reinforced Concrete Produced in factories with special machines and takes less time Need adequate equipment Costs required for transportation and installation need planning in the process of manufacture to transfer 1 Partially Precast Reinforced Concrete Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process and also at the location 1 Partially Precast Reinforced Concrete Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process and also at the location 2 Ready mix concrete Convenience in terms of greater flexibility in design and application It requires adequate equipment and manpower 2 Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement 2 Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement 3 Strict Quality Control concrete Consistent Quality Lots of workforce involvement 4 Strict Quality Control concrete Time and Energy Efficiency Limited dimensional accuracy	No.	Alternative	Potential Profits	Potential Losses
Precast Reinforced Concrete) Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process Concrete) Consistent Quality Need adequate equipment Ease in terms of greater flexibility in design and application Costs required for transportation and installation need planning in the process of manufacture to transfer Little workforce involvement Of manufacture to transfer Inimize construction costs Long service life and can be recycled again Environmentally friendly Damage can occur during the transportation or moving process and also at the location Pretially Precast Reinforced Concrete Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process and also at the location Intervention Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process Intervention Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process Intervention Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process and also at the location Intervention Consistent Quality Damage can occur during the transportation and installation		Initial		
Reinforced Concrete) Produced in factories with special machines and takes less time transportation or moving process Concrete) Produced in factories with special machines and takes less time Need adequate equipment Ease in terms of greater flexibility in design and application Need adequate equipment Little workforce involvement need planning in the process of manufacture to transfer Iminize construction costs Long service life and can be recycled again Protaced in factories with special Concrete Produced in factories with special machines and takes less time 1 Partially Precast Reinforced Concrete Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process and also at the location 1 Partially Precast Reinforced Concrete Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process and also at the location 1 Ready mix cast reinforced concrete Consistent Quality Costs required for transportation and installation need planning in the process of manufacture to transfer 2 Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement 2 Ready mix cast reinforced concrete Consistent Quality Lots of workforce in		Design		
Concrete) machines and takes less time Consistent Quality process Concrete) machines and takes less time Consistent Quality Need adequate equipment Costs Costs Ease in terms of greater flexibility in design and application Costs required for transportation and installation meed planning in the process of manufacture to transfer meed planning in the process of manufacture to transfer 1 Partially Precast Reinforced Concrete Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process and also at the location 1 Partially Precast Reinforced Concrete Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process and also at the location 1 Ready mix cast reinforced concrete Consistent Quality Costs required for transportation and installation need planning in the process of manufacture to transfer 2 Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement 2 Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement 2 Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement		(Precast		Damage can occur during the
Consistent Quality Need adequate equipment Ease in terms of greater flexibility in design and application Costs required for transportation and installation Interpret terms Little workforce involvement need planning in the process of manufacture to transfer Interpret terms Environmentally friendly Damage can occur during the transportation and installation need planning in the process of manufacture to transfer Partially Precast Reinforced Concrete Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process and also at the location Consistent Quality Produced in factories with special machines and takes less time Costs required for transportation and installation Convenience in terms of greater flexibility in design and application Costs required for transportation and installation Little workforce involvement Faster work need planning in the process of manufacture to transfer Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement Speed of Implementation Cannot be recycled again It takes longer in terms of mixing, pouring and drying the concrete Time and Energy Efficiency Limited dimensional accuracy Produced and poured at the project site Can be done in narrow areas Work and supervision is		Reinforced	Produced in factories with special	transportation or moving
2 Ease in terms of greater flexibility in design and application Costs required for transportation and installation need planning in the process of manufacture to transfer 1 Partially Precast Reinforced Concrete Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process and also at the location 1 Partially Precast Reinforced Concrete Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process and also at the location 1 Ready mix cast reinforced concrete Consistent Quality Damage can occur during the transportation or moving process and also at the location 2 Ready mix cast reinforced concrete Consistent Quality It requires adequate equipment and manpower 2 Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement 2 Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement 2 Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement 3 Speed of Implementation Cannot be recycled again It takes longer in terms of mixing, pouring and drying the concrete 4 Time and Energy Efficiency Limited dimensional acc		Concrete)	machines and takes less time	process
2 in design and application transportation and installation need planning in the process of manufacture to transfer 1 Partially Precast Reinforced Concrete Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process and also at the location 2 Ready mix cast reinforced concrete Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process and also at the location 2 Ready mix cast reinforced concrete Consistent Quality Damage can occur during the transportation and manpower 2 Ready mix cast reinforced concrete Consistent Quality Damage can occur during the transportation and installation 2 Ready mix cast reinforced concrete Consistent Quality Damage can occur during the transportation and installation 2 Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement 2 Speed of Implementation Cannot be recycled again It takes longer in terms of mixing, pouring and drying the concrete 2 Time and Energy Efficiency Limited dimensional accuracy 3 Trice and poured at the project site Can be done in narrow areas Work and supervision is more			-	Need adequate equipment
2 Ready mix cast reinforced concrete Consistent Quality Little workforce involvement need planning in the process of manufacture to transfer 2 Ready mix cast reinforced concrete Partially friendly Damage can occur during the transportation or moving process and also at the location 2 Ready mix cast reinforced concrete Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process and also at the location 2 Ready mix cast reinforced concrete Consistent Quality Costs required for transportation and installation need planning in the process of manufacture to transfer 2 Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement 2 Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement 3 Speed of Implementation Cannot be recycled again It takes longer in terms of mixing, pouring and drying the concrete 4 The and Energy Efficiency Limited dimensional accuracy 4 The and Energy Efficiency Limited dimensional accuracy			Ease in terms of greater flexibility	Costs required for
2 Little workforce involvement minimize construction costs Long service life and can be recycled again of manufacture to transfer 1 Partially Precast Reinforced Concrete Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process and also at the location 1 Partially Precast Reinforced Concrete Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process and also at the location 2 Consistent Quality Environmentally friendly It requires adequate equipment and manpower 2 Ready mix cast reinforced concrete Consistent Quality friendly Costs required for transportation and installation need planning in the process of manufacture to transfer 2 Ready mix cast reinforced concrete Environmentally friendly Lots of workforce involvement Speed of Implementation 3 Speed of Implementation Cannot be recycled again It takes longer in terms of mixing, pouring and drying the concrete 4 Time and Energy Efficiency Limited dimensional accuracy 4 Time and Energy Efficiency Limited dimensional accuracy 4 Tot be done in narrow areas Work and supervision is more			in design and application	transportation and installation
2				need planning in the process
2 Long service life and can be recycled again 1 Partially Precast Reinforced Concrete Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process and also at the location 1 Reinforced Concrete Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process and also at the location 2 Consistent Quality Equipment and manpower 2 Convenience in terms of greater flexibility in design and application Costs required for transportation and installation need planning in the process of manufacture to transfer Faster work Faster work minimize construction costs of manufacture to transfer Long service life and can be recycled again Environmentally friendly Lots of workforce involvement Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement Speed of Implementation Cannot be recycled again It takes longer in terms of mixing, pouring and drying the concrete Trime and Energy Efficiency Limited dimensional accuracy Produced and poured at the project site Can be done in narrow areas Work and supervision is more Limited dimensional accuracy			Little workforce involvement	of manufacture to transfer
2 Ready mix cast reinforced concrete Consistent Quality Damage can occur during the transportation or moving process and also at the location 1 Reinforced Concrete Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process and also at the location 1 Reinforced Concrete Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process and also at the location 2 Converteret Convenience in terms of greater flexibility in design and application Costs required for transportation and installation need planning in the process of manufacture to transfer 2 Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement 2 Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement 3 Speed of Implementation Cannot be recycled again 1 tt takes longer in terms of mixing, pouring and drying the concrete Time and Energy Efficiency 4 Time and Energy Efficiency Limited dimensional accuracy 4 Produced and poured at the project site Can be done in narrow areas 2 Work and supervision is more Limited dimensional accuracy <td></td> <td></td> <td>minimize construction costs</td> <td></td>			minimize construction costs	
Image: Partially Precast Reinforced Concrete Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process and also at the location 1 Reinforced Concrete Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process and also at the location 2 Concrete Convertence in terms of greater flexibility in design and application It requires adequate equipment and manpower 2 Convenience in terms of greater flexibility in design and application Costs required for transportation and installation need planning in the process of manufacture to transfer 2 Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement 2 Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement 3 Speed of Implementation Cannot be recycled again It takes longer in terms of mixing, pouring and drying the concrete 4 Strict Quality Control Time and Energy Efficiency Limited dimensional accuracy 4 Produced and poured at the project site Can be done in narrow areas Work and supervision is more			Long service life and can be	
1 Partially Precast Reinforced Concrete Produced in factories with special machines and takes less time Damage can occur during the transportation or moving process and also at the location 1 Reinforced Concrete Produced in factories with special machines and takes less time It requires adequate equipment and manpower 2 Convenience in terms of greater flexibility in design and application It requires adequate equipment and manpower 2 Ready mix cast reinforced concrete Environmentally friendly 2 Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement 5 Speed of Implementation Cannot be recycled again It takes longer in terms of mixing, pouring and drying the concrete 2 Time and Energy Efficiency Limited dimensional accuracy Produced and poured at the project site Can be done in narrow areaas Work and supervision is more			recycled again	
1 Precast Reinforced Concrete Produced in factories with special machines and takes less time transportation or moving process and also at the location 2 Consistent Quality It requires adequate equipment and manpower 2 Ready mix cast reinforced concrete Consistent Quality Costs required for transportation and installation 2 Ready mix cast reinforced concrete Environmentally friendly Lots of workforce involvement 2 Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement 5 Speed of Implementation Cannot be recycled again It takes longer in terms of mixing, pouring and drying the concrete 4 Time and Energy Efficiency Limited dimensional accuracy 7 Time and poured at the project site Limited dimensional accuracy			Environmentally friendly	
1 Reinforced Concrete Produced in factories with special machines and takes less time process and also at the location 1 Reinforced Concrete Produced in factories with special machines and takes less time process and also at the location 2 Convenience in terms of greater flexibility in design and application It requires adequate equipment and manpower 2 Convenience in terms of greater flexibility in design and application Costs required for transportation and installation 2 Ready mix cast reinforced concrete Environmentally friendly 2 Ready mix cast reinforced concrete Consistent Quality 2 Speed of Implementation Cannot be recycled again It takes longer in terms of mixing, pouring and drying the concrete Time and Energy Efficiency 4 Time and Energy Efficiency Limited dimensional accuracy Produced and poured at the project site Can be done in narrow areas Work and supervision is more Work and supervision is more		Partially		Damage can occur during the
Reinforced Concrete Produced in factories with special machines and takes less time process and also at the location It requires adequate equipment and manpower Convenience in terms of greater flexibility in design and application It requires adequate equipment and manpower Convenience in terms of greater flexibility in design and application Costs required for transportation and installation Ittle workforce involvement of manufacture to transfer need planning in the process of manufacture to transfer Faster work minimize construction costs of manufacture to transfer Long service life and can be recycled again Environmentally friendly Environmentally friendly Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement Speed of Implementation Cannot be recycled again It takes longer in terms of mixing, pouring and drying the concrete Strict Quality Control concrete Time and Energy Efficiency Limited dimensional accuracy Produced and poured at the project site Can be done in narrow areas Work and supervision is more	1	Precast		transportation or moving
2 Ready mix cast reinforced concrete Consistent Quality It requires adequate equipment and manpower 2 Ready mix cast reinforced concrete Consistent Quality Costs required for transportation and installation in need planning in the process of manufacture to transfer 2 Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement 3 Speed of Implementation Cannot be recycled again 4 It takes longer in terms of mixing, pouring and drying the concrete 5 Time and Energy Efficiency Limited dimensional accuracy 7 Produced and poured at the project site Can be done in narrow areas		Reinforced	Produced in factories with special	process and also at the
2 Consistent Quality equipment and manpower Convenience in terms of greater Costs required for Ittle workforce involvement need planning in the process of manufacture to transfer Faster work minimize construction costs of need planning in the process of Long service life and can be recycled again Environmentally friendly Environmentally friendly Environmentally friendly Ready mix cast cast finiforced Consistent Quality Lots of workforce involvement Speed of Implementation Cannot be recycled again It takes longer in terms of mixing, pouring and drying the concrete Strict Quality Control Concrete Time and Energy Efficiency Limited dimensional accuracy Produced and poured at the project site Can be done in narrow areas Work and supervision is more		Concrete	machines and takes less time	location
2 Convenience in terms of greater flexibility in design and application Costs required for transportation and installation need planning in the process of manufacture to transfer Faster work minimize construction costs Long service life and can be recycled again of manufacture to transfer Ready mix cast reinforced concrete Environmentally friendly Lots of workforce involvement Speed of Implementation Cannot be recycled again It takes longer in terms of mixing, pouring and drying the concrete Strict Quality Control Consrete Time and Energy Efficiency Limited dimensional accuracy Produced and poured at the project site Can be done in narrow areas Work and supervision is more Korken and supervision is more				It requires adequate
2 flexibility in design and application transportation and installation need planning in the process of manufacture to transfer Faster work Faster work minimize construction costs Long service life and can be recycled again Environmentally friendly Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement Speed of Implementation Cannot be recycled again It takes longer in terms of mixing, pouring and drying the concrete Strict Quality Control Concrete Time and Energy Efficiency Limited dimensional accuracy Produced and poured at the project site Can be done in narrow areas Work and supervision is more			Consistent Quality	equipment and manpower
2 Intervention Interventi			Convenience in terms of greater	Costs required for
2 Little workforce involvement Faster work minimize construction costs Long service life and can be recycled again Environmentally friendly of manufacture to transfer 2 Ready mix cast reinforced concrete Little workforce involvement Speed of Implementation Cannot be recycled again It takes longer in terms of mixing, pouring and drying the concrete Strict Quality Control Limited dimensional accuracy Produced and poured at the project site Time and Energy Efficiency Can be done in narrow areas Work and supervision is more			flexibility in design and application	transportation and installation
2 Faster work minimize construction costs Long service life and can be recycled again Environmentally friendly Ready mix cast reinforced concrete Consistent Quality Speed of Implementation Cannot be recycled again It takes longer in terms of mixing, pouring and drying the concrete Time and Energy Efficiency Limited dimensional accuracy Produced and poured at the project site Can be done in narrow areas Work and supervision is more				need planning in the process
2 minimize construction costs Long service life and can be recycled again Environmentally friendly Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement Speed of Implementation Cannot be recycled again It takes longer in terms of mixing, pouring and drying the concrete Strict Quality Control concrete Time and Energy Efficiency Limited dimensional accuracy Produced and poured at the project site Can be done in narrow areas Work and supervision is more Work and supervision is more			Little workforce involvement	of manufacture to transfer
2 Long service life and can be recycled again 2 Ready mix cast reinforced concrete Consistent Quality 2 Lots of workforce involvement Speed of Implementation Cannot be recycled again 1t takes longer in terms of mixing, pouring and drying the concrete Strict Quality Control concrete Time and Energy Efficiency Limited dimensional accuracy Produced and poured at the project site Can be done in narrow areas Work and supervision is more Work and supervision is more			Faster work	
2 recycled again Environmentally friendly 2 Ready mix cast reinforced concrete Consistent Quality Speed of Implementation Cannot be recycled again It takes longer in terms of mixing, pouring and drying the concrete Strict Quality Control concrete Time and Energy Efficiency Limited dimensional accuracy Produced and poured at the project site Can be done in narrow areas Work and supervision is more Work and supervision is more			minimize construction costs	
2 Environmentally friendly 2 Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement Speed of Implementation Cannot be recycled again It takes longer in terms of mixing, pouring and drying the concrete Strict Quality Control Time and Energy Efficiency Limited dimensional accuracy Produced and poured at the project site Can be done in narrow areas Work and supervision is more			Long service life and can be	
2 Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement Speed of Implementation Cannot be recycled again It takes longer in terms of mixing, pouring and drying the concrete Strict Quality Control Time and Energy Efficiency Limited dimensional accuracy Produced and poured at the project site Can be done in narrow areas Work and supervision is more			recycled again	
2 Ready mix cast reinforced concrete Consistent Quality Lots of workforce involvement Speed of Implementation Cannot be recycled again It takes longer in terms of mixing, pouring and drying the concrete Strict Quality Control Time and Energy Efficiency Limited dimensional accuracy Produced and poured at the project site Can be done in narrow areas Work and supervision is more			Environmentally friendly	
2 reinforced concrete Consistent Quality Lots of workforce involvement Speed of Implementation Cannot be recycled again It takes longer in terms of mixing, pouring and drying the concrete Strict Quality Control Time and Energy Efficiency Limited dimensional accuracy Produced and poured at the project site Can be done in narrow areas Work and supervision is more		Ready mix		
reinforced Consistent Quality Lots of workforce involvement Speed of Implementation Cannot be recycled again It takes longer in terms of It takes longer in terms of Strict Quality Control concrete Time and Energy Efficiency Limited dimensional accuracy Produced and poured at the project site Can be done in narrow areas Work and supervision is more	2	cast		
Speed of Implementation Cannot be recycled again It takes longer in terms of It takes longer in terms of Strict Quality Control concrete Time and Energy Efficiency Limited dimensional accuracy Produced and poured at the project site Can be done in narrow areas Work and supervision is more	Z	reinforced		
It takes longer in terms of mixing, pouring and drying the concrete Time and Energy Efficiency Limited dimensional accuracy Produced and poured at the project site Can be done in narrow areas Work and supervision is more Work and supervision is more		concrete	Consistent Quality	Lots of workforce involvement
Strict Quality Control mixing, pouring and drying the concrete Time and Energy Efficiency Limited dimensional accuracy Produced and poured at the project site Can be done in narrow areas Work and supervision is more Work and supervision is more			Speed of Implementation	Cannot be recycled again
Strict Quality Control concrete Time and Energy Efficiency Limited dimensional accuracy Produced and poured at the project site Can be done in narrow areas Work and supervision is more Work				It takes longer in terms of
Time and Energy Efficiency Limited dimensional accuracy Produced and poured at the project site				mixing, pouring and drying the
Produced and poured at the project site Can be done in narrow areas Work and supervision is more			Strict Quality Control	concrete
project site Can be done in narrow areas Work and supervision is more			Time and Energy Efficiency	Limited dimensional accuracy
Can be done in narrow areas Work and supervision is more			Produced and poured at the	
Work and supervision is more			project site	
			Can be done in narrow areas	
controlled			Work and supervision is more	
			controlled	
			Can be done in narrow areas	
			-	

Table 4. Analysis of the structure of Drainage Channel Rehabilitation Work

Calculations are relatively easy
and common

Feasibility Analysis

Table 5. Feasibility analysis of Drainage Channel Rehabilitation Work

	Drainage Channel Rehabilitation								
No.	Alternative					Total	Rank	Choose	
			В	С	D	Е	rotai		2
1	Partially Precast Reinforced Concrete	2	2	3	2	4	13	2	
2	Ready mix cast reinforced concrete	2	2	4	3	4	14	1	\checkmark

In the value feasibility analysis (table 5), there are several basic points that are used as an assessment. The assessment obtained is based on criteria assessed by Relative Weighting.

Relative weighting of Alternative Selection can be seen in table 6:

			С	riteria	a				
No.	Alternative		В	С	D	Е	Total	Rank	Choose
		10	8	6	4	2			
1	Partially Precast	2	2	3	2	4	68	2	
	Reinforced Concrete	20	16	12	8	8			
2	Ready mix cast		2	4	3	4	96	1	
	reinforced concrete		16	24	12	8		-	

Function Analysis

Work that has a cost/worth value > 1, then the work can be directly carried out by value engineering. For work that has a cost/worth < 1, a more in-depth study is required before the value engineering process is carried out. From Table 6, the function analysis of reinforced concrete with partial casting shows a cost/worth value of > 1, so this work can be carried out directly by value engineering (table 7).

		F	PERBANDINGAN		
N O	JOB DESCRIPTI ON	ENGINEER ESTTIMATE	VALUE ENGINEERING	DIFFERENCE	
		TOTAL PRICE (Rp)	TOTAL PRICE (Rp)	TOTAL PRICE (Rp)	

			Alternative 1	Alternative 2	Alternative 1	Alternative 2
1	Concrete Work	623.679.984, 00	467.106.327, 00	271.933.824, 09	156.573.657, 00	352.393.548, 00
		of work saved /E (%)	7,46	18,13		

Cost analysis after the work item was carried out by value engineering was obtained by alternative 2 which saved the most costs on concrete work on the Drainage Channel Rehabilitation Work project, namely IDR 352,393,548.00 with the percentage of work saved with VE (%) being 18.13%.

Presentation

The results of Value Engineering on Drainage Channel Rehabilitation Work on concrete work items can be seen in the following table 8:

NO.	JOB DESCRIPTION	TOTAL PRICE (Rp)	TOTAL PRICE (Rp)
A	Preparatory work	101.254.900	101.254.900
В	Earthworks	272.912.010	272.912.010
с	Concrete Work	1.452.366.184	1.100.620.024
D	Piling Work	67.192.500	67.192.500
Е	Iron And Aluminum Works	206.160.250	206.160.250
	TOTAL JOB PRICE	2.099.885.844	1.748.139.684
	PRESENTATION OF SAVINGS		16,78 %

Table 8. Results of overall cost percentage after VE

The overall project cost for the initial plan is IDR 2,099,885,844, while the overall project cost after Value Engineering is IDR. 1,748,139,684. The costs saved are IDR 352,393,548.00 or 16.78% of the total project.

CONCLUSION

Based on the results of the research and discussion described in the previous chapter, it can be concluded that:

- 1. Several alternatives used in VE for concrete work in the Drainage Channel Rehabilitation Work Project, Smarinda Ulu District:
 - a. Partially Precast Reinforced Concrete
 - b. Ready mix cast reinforced concrete
- 2. Cost savings obtained from the application of Value Engineering in concrete work are:

- a. The cost of concrete work, namely at the beginning or according to plan, is Rp. 623,679,984.00 Costs for concrete work after VE, namely Rp. 271,933,824.09 With costs saved amounting to Rp. 352,393,548.00 or 18.3%.
- b. The overall project cost for the initial plan is IDR 2,099,885,844, while the overall project cost after VE is IDR 1,748,139,684. With the cost savings of Rp. Rp. 352,393,548.00 or 16.78% of the total project.

REFERENCES

- Adianto. 2022 "Penerapan Value Engineering pada Proyek Pembangunan Gedung Serbaguna X Di Kota Medan," Journal Of Sustainable Construction, Vol. 2, No. 1, Pp. 10-18.
- Aliman. 2000 Modul Ekonometrika Terapan. Pau Studi Ekonomi Ugm. Yogyakarta.
- Astina, I.. 2015. Value Engineering Antara Perancah Konvensional Dengan Scalfolding Pada Proyek Konstruksi (Studi Kasus Pada Gedung Bertingkat Di Smpn 10 Denpasar Bali). Teknik Sipil Untag Surabaya,.
- Austen, Dan R.H. Neale, 1994, Manajemen Proyek Konstruksi Pedoman, Proses Dan Prosedur, Ppm Dan Pt Pustaka Binaman Pressindo, Jakarta.
- Berawi, M.A. 2014. Aplikasi Value Engineering Pada Industri Konstruksi Bangunan Gedung. Jakarta, .
- Bertolini, V. 2016. Aplikasi Value Engineering Pada Proyek Pembangunan Gedung (Studi Kasus Hotel Grand Banjarmasin). Jurnal Iptek.
- Dajan A. 1986. Pengantar Metode Statistik, Jilid 1 dan 2. LP3ES, Jakarta.
- Djoko MH , 2016 Sumber Air baku Untuk Air Minum Artikel.
- Iskandar, 2016. Penerapan Rekayasa Nilai (Value Engineering) pada Pekerjaan Struktur Balok dan Kolom Gedung Poliklinik Universitas Brawijaya Malang. Jurnal Prosiding Temu Ilmiah IPLBI 2016 H 185
- Lies K Wulandari, 2019.Model Fisik Pengolahan Limbah Blackwater pada Septictank Komunal,Dream Litera Buana, Malang ISBN 978-602-5518-78-2M
- Mahyuddin. 2022. "Analisa Rekayasa Nilai (Value Engineer) Pada Konstruksi Bangunan Rumah Dinas Puskesmas Karang Jati Balikpapan," Journal.Unifa.Ac.Id, No. 1, P. 5.
- M. Mahyuddin. 2020. "Analisa Rekayasa Nilai (Value Engineer) Pada Konstruksi Bangunan Rumah Dinas Puskesmas Karang Jati Balikpapan," Acta, M Mahyuddin - Journal Techno Entrepreneur, Vol. Vol. 5, P. 1
- Nicolau Martins Soares, 2017. "Aplikasi Value Engineering Pekerjaan Struktur Pada Proyek Pembangunan Mall Dinoyo City Malang," Jurnal Penelitian Teknik Sipil, Vol. 4, No. 47-57, P. 1,
- Nasrul. 2021. "Aplikasi Value Engineering Pada Proyek Konstruksi (Studi Kasus Proyek Pembangunan Gedung Kuliah lain Imam Bonjol Padang) Tahun 2017," Jurnal Teknik Sipil Itp, Vol. 4, No. 1, Pp. 47-57.
- Oscar dan Nasrul, 2017. Aplikasi Value Engineering Pada Proyek Konstruksi (Studi Kasus Proyek Pembangunan Gedung Kuliah lain Imam Bonjol Padang). Jurnal Teknik Sipil ITP Vol. 4 No.1 Januari
- Ricky Kristo Ngantung. 2021. "Penerapan Value Engineering Dalam Upaya Meningkatkan Efisiensi Biaya Proyek Pada Pembangunan Gedung Dprd Sulawesi Utara," Jurnal Ilmiah Media Engineering, Vol. 11, No. 1, Pp. (51-58.

- Saputra, . "Penerapan Value Engineering Pada Pekerjaan Konstruksi Studi Kasus Proyek Pembangunan Rumah Sakit Umum Provinsi Sumatera Selatan," Jurnal Forum Mekanika, Vol. 7, No. 2
- Sukmawati Santika Arina Musliha. 2021. "Analisis Value Engineering Pada Struktur Bangunan Denganmetode Analytical Hierarchy Process (Ahp)," Jurnal Matriks Teknik Sipil, Vol. 8, No. 4, Pp. 44-52.
- Samsul Rizal, 2012, Analisis Faktor-Faktor Yang Mempengaruhi Tidak Tercapainya Waktu Kontrak Pada Proyek-Proyek Pembangunan Rumah Susun Sederhana Sewa Di Provinsi Jawa Timur. Tesis ITN Malang.
- Soeharto, I, 2001. Manajemen Proyek Dari Konseptual Sampai Operasional. Erlangga, Jakarta.Nguyen, P. H. L., Kuruparan, P., & Visvanathan, C. (2007). Anaerobic digestion of municipal solid waste as a treatment prior to landfill. Bioresource Technology, 98(2), 380–387. https://doi.org/10.1016/J.BIORTECH.2005.12.018
- Pestaño, L. D. B., & Jose, W. I. (2016). Production of Solid Fuel by Torrefaction Using Coconut Leaves As Renewable Biomass. International Journal of Renewable Energy Development, 5(3), 187–197. https://doi.org/10.14710/ijred.5.3.187-197
- Qonitan, F. D., Suryawan, I. W. K., & Rahman, A. (2021). Overview of Municipal Solid Waste Generation and Energy Utilization Potential in Major Cities of Indonesia. Journal of Physics: Conference Series, 1858(1). https://doi.org/10.1088/1742-6596/1858/1/012064
- Sarwono, A., Septiariva, I. Y., Qonitan, F. D., Zahra, N. L., Sari, N. K., Fauziah, E. N., Ummatin, K. K., Amoa, Q., Faria, N., Wei, L. J., & Suryawan, I. W. K. (2021). Municipal Solid Waste Treatment for Energy Recovery Through Thermal Waste-To-Energy in Depok City, Indonesia. Journal of Advanced Research in Fluid Mechanics and Thermal Sciences, 85.
- Septiariva, I. V. A. Y., & Suryawan, I. W. K. (2021). Development of water quality index (WQI) and hydrogen sulfide (H2S) for assessment around suwung landfill, Bali Island. Journal of Sustainability Science and Management, 16(4), 137–148.
- Sofiyah, E. S., & Suryawan, I. W. K. (2021). Cultivation of Spirulina platensis and Nannochloropsis oculata for nutrient removal from municipal wastewater. Rekayasa, 14(1), 93–97. https://doi.org/10.21107/rekayasa.v14i1.8882
- Sugni, M., Calcaterra, E., & Adani, F. (2005). Biostabilization-biodrying of municipal solid waste by inverting air-flow. Bioresource Technology, 96(12), 1331–1337. https://doi.org/10.1016/J.BIORTECH.2004.11.016
- Suryawan, I. W. K., Wijaya, I. M. W., Sari, N. K., & Yenis, I. (2021). Potential of Energy Municipal Solid Waste (MSW) to Become Refuse Derived Fuel (RDF) in Bali Province, Indonesia. Jurnal Bahan Alam Terbarukan, 10(200).
- Ulhusna, N. (2022). Bio-concentration for industry. International Journal 4(1), 121-130.
- Widyarsana, I. M. W., Damanhuri, E., Ulhusna, N., & Agustina, E. (2020). A Preliminary Study: Identification of Stream Waste Quantity and Composition in Bali Province, Indonesia. 5.



© 2024 by the authors. Submitted for possible open access publication under the terms and conditions of the Creative Commons Attribution (CC BY SA) license (https://creativecommons.org/licenses/by-sa/3.0/).